Marco FRIIA C Install Checklist

Marco Beverage Systems *requires that the following conditions are met before installation of the* ***FRIIA C Hands-Free system*** *can begin. Failure to meet these conditions may result in multiple visits by installers, the cost of which will not be covered by* ***Marco Beverage Systems****.*

SITE READINESS

- ✓ There should be a minimum of 2 inches of space on all sides of the Chiller/Carbonator unit to provide adequate air flow.
    - Minimum dimensions for cabinetry are 14 in. wide x 24 in. deep x 32 in. high.
- ✓ The area above the font location must be open. Ensure at least 18 inches of clearance below any high cabinetry.
- ✓ The installation site should be safe, clean, and clear of all construction debris.
- ✓ The site should no longer be an active construction zone.

POWER

- ✓ 110v AC service with NEMA 5-15 receptacle within 5 feet of installation location.
- ✓ Power must be live to the outlets before installation.

VENTILLATION

- ✓ Ventilation grills of at least 2 in. x 6 in. installed in two locations.
    - Ideal placement is one low and the other high for optimum performance.

WATER

- ✓ Dedicated 3/8” water supply line with shut off valve in place.
- ✓ Appropriate water filtration for the install location should be in place.
  - Water hardness should not exceed 5 grains per gallon.
  - Chlorides should be less than 30ppm.
- ✓ Incoming water pressure should be greater than 30 psi.
- ✓ If water lines and/or filtration are newly installed, ensure that the system is thoroughly purged before installation.

COUNTERTOP

- ✓ Holes must be present.
  - 1 ½ inch for the font
  - 4 inch for the drip tray

  See Font install manual for cutsheet
- ✓ Counter thickness should not exceed 60mm

DRAINAGE

- ✓ Drain should be located within one meter of the drip tray.
- ✓ Drain must be installed below the level of the drip tray basin.

For questions, support, or additional resources – please reach out to Marco US Support.

us.support@marcobeveragesystems.com | +1 206-641-7677